# BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

## APPROVED SCHEDULE - B

**Issued to :**

**Original / Duplicate**
**Item No.**

**Name of the Work : Improvements to Footpath in Ward No. 09, Vidyaranyapura Sub Division.**

| Sl. No. | Approved Qty. | Description | Unit | KRIDL | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 1 | 167.25 | Earth work excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work | cum | 90.72 | Rupees Ninety and Seventy Two Paise Only |
| 2 | 450.00 | Removing B.S Slab of Drain and stacking etc complete as per specifications and directions of engineer in charge of the work | Sqm | 50.11 | Rupees Fifty and Eleven Paise Only |
| 3 | 360.00 | Refixing stone slabs of drains and pointing in C.M (1:3) etc complete as per specifications and directions of engineer in charge of the work | Sqm | 70.04 | Rupees Seventy and Four Paise Only |
| 4 | 90.00 | Providing **granite slabs** of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete 7.5 cms thick etc complete as per specifications and directions of engineer in charge of the work | Sqm | 343.44 | Rupees Three Hundred Forty Three and Forty Four Paise Only |
| 5 | 108.00 | Providing and **constructing granite / trap / basalt size stone masonry** in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work | cum | 5307.12 | Rupees Five Thousand Three Hundred Seven and Twelve Paise Only |
| 6 | 27.00 | Providing and laying in position plain cement concrete of **mix M15 with cement @ 240 kgs with 20mm** and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications | Cum | 4779.00 | Rupees Four Thousand Seven Hundred Seventy Nine Only |
| 7 | 67.50 | **Providing and laying cement concrete** using 20mm and down size granite course aggregates and fine aggregates of **ready mixed concrete for R.C.C works** laid in 15cms thick layers and well compacted including vibrating curing etc., including smooth finish in CM 1:3,with all lead and lift etc., complete. (exclusive of cost of steel and fabrication charges) Ready mixed cement concrete for Beams, column, Staircase and Roof with M-20(cement -320 Kg/Cum) etc complete as per specifications and directions of engineer in charge of the work | **Cum** | 6348.34 | Rupees Six Thousand Three Hundred Forty Eight and Thirty Four Paise Only |

EXECUTIVE ENGINEER-4
KRIDL, BBMP, DIVISION,
BANGALORE-560 010

| Sl. No. | Approved Qty. | Description | Unit | KRIDL | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 8 | 47.25 | **Providing T.M.T steel reinforcement for R.C.C work** including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications.Specification No. KBS 4.6.3 -do- for TMT Bars Fe 415 page etc complete as per specifications and directions of engineer in charge of the work | **qtl** | 7244.04 | Rupees Seven Thousand Two Hundred Forty Four and Four Paise Only |
| 9 | 240.00 | **Providing and removing centering,** shuttering, strutting, propping etc., and removal of form work for **columns,** pillars, piers, post and struts, circular or curved in plan including cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work | **sqm** | 836.34 | Rupees Eight Hundred Thirty Six and Thirty Four Paise Only |
| 10 | 105.00 | Providing and applying painting two coats (excluding priming coat) on new wood surface and / or wood based surface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost of materials, labour, etc complete as per specifications and directions of engineer in charge of the work | Sqm | 79.92 | Rupees Seventy Nine and Ninety Two Paise Only |
| 11 | 125.44 | Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading etc complete as per specifications and directions of engineer in charge of the work | Cum | 72.71 | Rupees Seventy Two and Seventy One Paise Only |

**I am prepared to execute the above mentioned work written by me in Schedule - B**

**Contractor Signature**
**Reg. No.**
**Postal Address**

EXECUTIVE ENGINEER-4
KRIDL, BBMP, DIVISION,
BANGALORE-560 010

**Executive Engineer**
**Byatarayanapura Division**
**BBMP, Bangalore - 92**